

Quotation: E-19003-rev4

Reference: PR-19513

**CAST RESIN TRANSFORMER**

**2500 kVA**

Losses Family		Special	Installation		indoor
Vector group		Dyn11	Type of cooling		AN
Frequency	Hz	50	Installation altitude	m.s.l	<1000
Phases		3	Total harmonic distortion	THDv	<5%

	HV Winding	LV1 Winding	LV2 Winding
Nominal rated power at cont. Service	2500kVA	2500kVA	
Nominal voltage (at no load)	33kV	400V	
Off-load tapping links	± 2 x 4,54 %		
Connection	Delta	Star	
Insulation class [kV]	36	≤ 1,1	
AC [kv]	70	3	
BIL [kV]	170	-	
Winding material	Al	Al	
Type of winding	Cast in mould under vacuum	Impregnated under vacuum	

**INSULATION AND TEMPERATURE CLASS**

Max Ambient temperature °C

40

	HV Winding	LV1 Winding	LV2 Winding
Insulation temperature class	°C	155°C (F)	155°C (F)
Temperature rise of windings	K	100	100
Environmental, Climatic, Fire classes	E2-C2-F1		(Type Test Certificate CESI A9032391)

**GUARANTEED VALUES AT VOLTAGE RATIO OF:**

33000 / 400 V

( Tolerances according to the mentioned Standards )

2500 kVA

	W	5800	Tolerance, Po	%	15%
No-load loss, Po	W	5800	Tolerance, Po	%	15%
No-load current, Io	%	0,7	Tolerance, Io	%	30%
Load loss, °C	W	25000	Tolerance, °C	%	15%
Impedance voltage, Uk	%	6	Tolerance, Uk	%	±10%
Partial discharge value	pC				<10
Sound level Power, Lwa	dB(A)				81

**OVERALL DIMENSIONS AND WEIGHTS (Preliminary)**

Length x Width x Height (IP00)	mm	2200	1400	2560	CRT Mass [kg]	6050
Length x Width x Height (IP31)	mm				Box Mass [kg]	
Rollers distance	mm	1070 x 1070				

**PAINTING (subject to availability)**

Magnetic core	RAL	9005	Box	RAL
Frames	RAL	9005		

According to IEC 60076-11

---

---

**ACCESSORIES AND TESTS**

---

---

In the price quoted, is included a set of routine tests at our test room according to IEC 60076-11 standard. For each transformer, a specific Test Report will be issued

Code Nr.	Description	Qty	Unit price CRT
-	HV terminals	3	Included in the price
-	LV bus bar terminals	4	Included in the price
-	Off load tapping links	3	Included in the price
-	Rating plate	1	Included in the price
-	Lifting lugs	4	Included in the price
-	Earth terminals	2	Included in the price
-	Orientable rollers	4	Included in the price
200074	3 Pt100 probes wired to terminal box IP65 >=2500	1	Included in the price
220023	MT200 LITE CONTROL UNIT	1	Included in the price
CB01412	+40% kVA. Temporary Increase ventilation bars 50Hz	1	Included in the price
190020	NYLON ROLLER DIA 200	4	Included in the price
	Antiseismic transformer AG2 (1000kVA-3150kVA)		

**Notes**

---

---

---

---

---

---

---

---

---

---

Antiseismic frame (Horizontal Peak Ground Acc): <=0.2g (light earthquakes)